



**VILLAGE OF
EL PORTAL**

500 NE 87th Street
El Portal, FL 3318
<https://elportalvillage.com/>
305-795-7880

HURRICANE WARNING PROCEDURE FOR ALL CONSTRUCTION SITES

1. All fixed tower cranes must set boom on free spinning.
2. All portable truck cranes must lower boom to the ground.
3. All portable construction equipment shall be secured or removed from construction site.
4. All construction material to be bundled and secured or stored offsite.
5. Loose roof tile shall be bundled and secured to roof or removed from roof and stored inside of building or offsite.
6. All dumpsters to be emptied or covered securely with a tarp.
7. Port-o-lets to be lowered to the ground and secured or removed from building site.
8. No construction equipment or material is to be stored in a construction trailer.

Any material or equipment that is left on a construction site that may become a flying missile during a hurricane will be removed by the order of the North Bay Village Building Official, and appropriate fees and fines will be levied.

Building Official